



**SECTION A-A**

**NOTES**

1. CONTRACTOR TO VERIFY OD PRIOR TO ORDERING TRANSITION COUPLING.
2. COUPLINGS TO BE SIZED TO FIT ROUGH BARREL OF AC PIPE.
3. CONTRACTOR TO SCHEDULE SHUT DOWN OF EXISTING WATERLINE WITH THE CITY OF GASTONIA UTILITIES DEPARTMENT.
4. WATERLINE REPLACEMENT AND SERVICE SHALL BE RESTORED THE SAME DAY AS REMOVAL OF THE EXISTING LINE.
5. CONTRACTOR SHALL NOTIFY ALL RESIDENTS IN WRITING OF THE EXACT TIMES WATER SERVICE WILL BE INTERRUPTED.
6. FLOWABLE FILL SHALL HAVE A MIN. 7-DAY COMPRESSIVE STRENGTH OF 100 PSI AND MAX. OF 200 PSI.
7. VIBRATORY COMPACTION SHALL NOT BE PERFORMED WITHIN 10 FEET OF THE EXISTING AC WATERLINE.
8. ALL AC PIPE REMOVAL AND DISPOSAL SHALL BE TO NESHAP REQUIREMENTS.

REVISED 11/2/2023	DATE: AUG. 1, 2018	<b>Standard Detail</b>	OFFICE OF THE
	SCALE: NONE		CITY ENGINEER
	DRAWN BY: TAJ, MGB	<b>Repair Detail for Asbestos Cement Pipe</b>	GASTONIA, N.C.
	CHECKED BY: TAJ, JB		FILE NO. <b>71B-46</b>
	CITY ENGINEER: GVS		